

## Oceana Bal Harbour

Miami, United States

Basement excavation for high rise residential building on Miami Beach, Florida.



### The project

A 28-story residential high-rise planned for construction on Miami Beach included a 3-story below-grade parking garage. The area of the excavation footprint was 107,000 square feet and the excavation depth reached 40 feet below grade.

### The challenge

The 40-foot deep basement excavation was 34 feet below sea level, posing the significant challenge of controlling groundwater inflow, especially due to the native porous oolitic limestone.

## The solution

Keller solved the groundwater control challenge by using deep soil mixing to create a seepage barrier along the perimeter and base of the excavation. The perimeter soil mix columns also provided excavation support as they were reinforced with steel H-piles and laterally restrained with tieback anchors or internal bracing. Keller also designed and installed large-diameter auger cast piles as deep as 85 feet below the excavation to support the structural loads and act as tiedown anchors for resisting the hydrostatic uplift on the soilcrete bottom slab.

## Project facts

### Owner(s)

Consultatio Real Estate

### Keller business unit(s)

Keller North America

### Main contractor(s)

Coastal Construction

### Solutions

Seepage control  
Excavation support  
Heavy foundations

### Markets

Residential

### Techniques

Anchors - single bond length  
Wet soil mixing  
CFA piles (auger cast)